### **CARRIAGE TRAILS**


MVRPC Presentation March 12, 2025


#### **CONTENTS**

- 1. Aerial of Carriage Trails and surrounding area
- 2. Overview of Carriage Trails and the additional annexed acreage
- 3. Record annexation plat
- 4. Existing sanitary sewer stubs
- 5. Brandt sewer study Singer Road concept
- 6. Miami County denial letter
- 7. Overview of Carriage Trails section 20 phase I
- 8. Build out schedule









### ANNEXATION TO THE THE CITY OF HUBER HEIGHTS STATE OF OHIO, COUNTY OF MIAMI, TOWNSHIP OF BETHEL SECTIONS 13, 14, 19 & 20, TOWN 2, RANGE 9, MRS

VOLUME 30 PAGE 81 -A
MIAMI COUNTY RECORDER'S RECORD OF PLATS



LEGEND


RON PIN FOUND (AS NOTED)

MAG NAIL FOUND

IRON PIN SET 5/8" REBAR 30" LONG "IBI GROUP S-6872/S-7740"

ACREAGE BREAKDOWN BY SECTION SECTION 13: 103.682 ACRES

SECTION 13: 103.682 ACRES SECTION 14: 35.867 ACRES SECTION 19: 134.161 ACRES SECTION 20: 22.526 ACRES TOTAL: 296.236 ACRES





MARCADIS IBI GROUP


8101 M. High Street Columbus, DH 43255 Contact: DAVE CHTESA 514 818-4900 ext. 2039 Fax: 614-818-4902 www.ibigroup.com


2/2

#### RECORD PLAT











Bricker Graydon LLP 2 East Mulberry Street Lebanon, OH 45036 513.870.6700 Office www.brickergraydon.com Amelia Blankenship Of Counsel 513 870 6579 Direct Phone ablankenship@brickergraydon.com

October 25, 2024

Sent via email and regular mail

Joseph R. Miller Vorys 52 East Gay Street P.O. Box 1008 Columbus, OH 43216 jrmiller@vorys.com

: Sanitary Sewer Service to Carriage Trails II

Mr. Miller:

I am writing to you on behalf of Michael Clarey, Miami County Administrator. Mr. Clarey asked I respond to your letter dated October 16, 2024. You are correct in your statement that Miami County will not be providing sanitary sewer service to the Carriage Trails II development in Huber Heights. The County will participate in discussions regarding amendments to the Facility Planning Area to accommodate sanitary sewer service to the planned Carriage Trails II development.

Sincerely,


Amy Blankenship

cc: Michael Clarey, Miami County Administrator



### BUILD OUT SCHEDULE

<u>YEAR</u>	BUILDING LOTS DEVELOPED	BUILDING LOTS SOLD	INVENTORY	HOMES FINISHED & CONNECTED TO SANITARY SEWER	TOTAL HOMES CONNECTED TO SANITARY BY 2030	TOTAL HOMES CONNECTED TO SANITARY BY 2040
2024	0	0	0	0		
2025	125	20	105	10		
2026	50	45	110	40		
2027	50	70	90	60		
2028	50	80	60	75		
2029	50	90	20	90	275	
2030	100	90	30	90		
2031	100	90	40	90		
2032	100	100	40	90		
2033	100	100	40	100		
2034	100	100	40	100		
2035	100	100	40	100		
2036	100	100	40	100		
2037	100	100	40	120		
2038	100	120	20	120		
2039	100	120	0	120		
2040	100	100	0	120		1425
	1425	1425		1425		



# Tri-Cities North Regional Wastewater Authority

Capital Improvement Project Update







### Plant Upgrade Projects

- 1. EQ and Collection System Improvement Project Update
- 2. Plant Improvement / Expansion Project Update
- 3. Questions



## EQ and Collection System Improvement Project








### EQ and Collections System Improvements

### **Project Goals**:


- Achieve long-term state and federal EPA compliance- eliminate all Sanitary Sewer Overflows (SSO)
- Increase collection system capacity during extreme wet weather events
- Eliminate the possibility of sewage in basements
- Increase system reliability and resiliency
- \$24.1M project. Construction to be complete by December 2025






Under construction in the Taylorsville Metro Park, south of US 40 in Vandalia.

### Interceptor Sewer Line Improvements- Phase 2









### Plant Improvement Project






### Plant Improvement Project

#### **Project Goals**:

- Encourage economic development via increased wastewater treatment services
- Comply with future Total Phosphorus, along with stricter Ammonia, BOD (biochemical oxygen demand) effluent limits from OEPA
- Increase plant flow capacity from 11.2 MG to 17.3 MG, to address growing communities
- Update grit removal system
- Convert two-stage trickling filter system to activated sludge
- Address aging infrastructure
- Improve antiquated and inefficient treatment processes





#### **Proposed Upgrades**

#### Legend

#### EXISTING LAYOUT

- A. MAIN PUMP BUILDING WITH ROUGH BAR SCREENS
- B. GRIT REMOVAL
- C. PRIMARY CLARIFIERS
- D. RANDOM MEDIA TRICKLING FILTERS
- E. INTERMEDIATE CLARIFIERS
- F. NITRIFICATION TOWERS
- G. FINAL CLARIFIERS
- H. CHLORINE CONTACT TANK
- I. FINAL EFFLUENT BUILDING
- J. SLUDGE THICKENER
- K. SLUDGE DIGESTERS

#### **PROPOSED**

PROPOSED CHANGE

PROPOSED DEMOLITION

REPLACE EQUIPMENT

#### Proposed Upgrades

Item	Recommendation	Opinion of Capital Costb
Coarse Screening + Building	Replace screen and add building	\$2,594,000
Influent Pump Stationa	Replace two small pumps with larger pumps <sup>a</sup> ; replace piping	\$5,441,000
Fine Screening + Building	New fine screens in new building	\$11,663,000
Grit Removal	New vortex grit basins and new grit dewatering	\$4,872,000
Primary Clarification and Equalization Mixing	Replace mechanisms and drives; Replace existing aeration with submersible mixers	\$7,938,000
Biological Treatment	Replace 2-stage filters with BNR activated sludge	\$48,331,000
WAS Thickening and Storage	New GBTs, WAS and TWAS storage	\$18,140,000
Peak Flow Management	Upgrade post aeration tank and outfall; Add effluent PS with Head Box	\$13,647,000
Digester Upgrades	Add boiler, Rehab covers, Provide heating for secondary digester	\$5,700,000
Misc. Site Demolition		\$1,000,000
Electrical Service Upgrade	Placeholder until electrical needs are defined	\$2,130,000
Opinion of Total Project Cost		\$121,816,000

<sup>a</sup>Assumed firm capacity = 35 MGD

### Plant Improvement Project

### **SCHEDULE**

Milestone	Date	
Request for Proposals Released	November 8th, 2024	
Geotechnical Field Work	Mid December 2024	
Proposals Due	December 18th, 2024	
Interviews with Proposers	Early January 2025	
CMAR Awarded	February 1st, 2025	
Begin Pre-construction Phase	April 1st, 2025	
DEFA Construction Loan Application Date	August 2025	
100% Design Submittal	June 2026	
Construction	Mid 2026-2029	

